

ADDENDUM NO. 2

Page No. 1 of 2

Date: May 22, 2025

PROJECT: DISTRICT OF MACKENZIE PUBLIC WORKS ASPHALT and CONCRETE WORKS - 2025
LOCATION: District of Mackenzie
OWNER: District of Mackenzie

This Addendum is issued prior to the close of the RFP to revise and/or clarify parts of the Contract Documents. This Addendum is part of the Contract Documents and in the case of conflict with the balance of the Documents, this Addendum shall govern.

1. Bonding.

Bid Deposit

Bid Deposit in the form of a certified cheque from a Chartered Canadian Bank or a Bid Bond, or an equivalent form acceptable to the Owner. The Bid Bond shall be in the amount of ten (10) percent of the Bid Sum and shall be made payable to the Owner.

The proponent shall forfeit all or a part of this Deposit as liquidated damages should he refuse or neglect to sign the Contract Agreement and provide the specified Performance Bond, and Labor and Material Payment Bond within a period of fourteen (14) calendar days after receiving notice of award.

Material and Performance Bond.

Prior to award of contract, the proponent shall be required to give to the Owner in a form acceptable to the Owner, both a Performance Bond and a Labour and Materials Payment Bond, each in the amount of fifty percent (50%) of the estimated Contract Value, as defined by the notice the award.

These Bonds shall be provided by a surety company authorized to do business in the Province where the Work is to be carried out.

2. Attendance at Site Visit.

Terus Construction.
Pittman Asphalt.

3. Overlay Thickness.

The reference to thickness in the spreadsheet column for Rehab Activity is superseded by the note at the bottom of the spreadsheet. Overlay Thickness are as follows:

Thin	40mm
Moderate	65mm
Thick	65mm

The thick overlay is proposed done at 65mm to maximize the streets that can be resurfaced.

Tonnage estimates are based on these thicknesses.

4. Edge milling.

Edge milling will target 50mm depth by 2.2m

5. Structural Patching

Structural Patching will be an 100mm thick Asphalt Base Course (ABC) overlaid by 50mm when the patch is in isolation. Or overlain by the associated thickness when performed in conjunction with a full street resurfacing.

6. Estimated scope.

The work program proposed by the RFP is based on what is anticipated achievable using an estimated cost. The successful proponent will be expected to work with the District to finalise the work program following notice of award, and prior to notice to proceed.

End of Addendum 2